

City of Frankfort Awards Paving Bid and Paving Plans for 2022

Frankfort, IN – Twenty-three projects will be completed during 2022 using a combination of local funds and funding awarded through Indiana's Next Level Roads: Community Crossings matching grant.

Mayor Sheets, Board of Public Works members, and Street Superintendent Jason Forsythe approved the total of \$912,716.72 for 2022. The following paving projects will begin at the end of March or the beginning of April (weather permitting):

- Monon Street from Washington to Clinton Street
- Williams Road from Wabash Street to Forest Drive
- Freeman Street from Jackson Street to 5th Street
- 4th Street from Freeman to Short 4th Street
- 4th Street from Walnut to Armstrong
- Outer Drive from Crescent to Clinton Street
- Hawthorne Avenue from Barner to Kyger
- Rowe Street from Rossville Avenue to Paris Street
- Morrison Street from Pratt to Myrtle
- Sims Street from Washington to East McClurg
- East McClurg Street from Sims to Clay Street
- East Paris Street from Jackson Street to Clay Street
- Vermont Street (off Williams Street, runs in front of Indiana Packers)
- Harrison Street from Walnut to South Street
- Jefferson Street from Main to Railroad
- Harrison Street from Kyger to Green Street
- McKinley Avenue from Walnut to Frankfort Truck and Car
- Short Myrtle from McKinley to Walnut
- Boomer Street from McKinley to Walnut
- Calloway Avenue from McKinley to Walnut
- Eastwood Drive from Harvard to Dead End South of Harvard
- Indiana Street from 3rd Street to 2nd Street
- Aughe Street from Washington to Clinton Street

"I appreciate everything that Jason Forsythe has done for the City and the Street Department. Because of his efforts, we have been able to save the City of Frankfort thousands of dollars and was able to pave more roadways," stated Mayor Sheets. "The Community Crossing matching grant has played an important part in our infrastructure and helped us maintain our roads over the past few years. Thank you Jason."

Reith Riley was awarded Frankfort's paving projects at the December 30, 2021 Board of Public Works Meeting. To see how the cost per project has been broken down, please visit The City of Frankfort's website.

"I want to personally thank Mayor Sheets, Board of Public Works, as well as City Council for their time and appropriating funds for us to use towards the application for these 23 projects. All of the roadways listed were considered 2-rated roads on the Paser Scale as part of the City of Frankfort Asset Management Plan – required for the grant process. A ten on the Paser Scale is equivalent to the revitalized Washington Avenue and zero is considered the worst," add Jason Forsythe.

####

For additional questions please contact Jason Forsythe at 765.659.2912

PROJECT 01 - Monon Street (Washington - Clinton Street)

Street
Monon Street
Length (FT)
664

From St.
Washington
Width (FT)
36

To. St.
Clinton
Area (SY)
2,632

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	17	TON	\$100.00	\$1,700.00
3	HMA PATCHING, TYPE B	14.5	TON	\$150.00	\$2,175.00
4	MILLING, ASPHALT, 2 IN.	2632	SYS	\$2.16	\$5,571.20
5	MILLING, APPROACH	0	SYS	—	—
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	290	TON	\$75.00	\$21,750.00
7	JOINT ADHESIVE, SURFACE	664	LFT	\$0.80	\$531.20
8	LIQUID ASPHALT SEALANT	664	LFT	\$0.20	\$132.80
9	ASPHALT FOR TACK COAT	0.7	TON	\$50.00	\$35.00
10	HMA FOR APPROACHES, TYPE B	0	TON	—	—
11	CASTING, ADJUST TO GRADE	3	EACH	\$0.01	\$0.03
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1328	LFT	\$1.35	\$1,660.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	0	LFT	—	—
				TOTAL	\$37,643.20

PROJECT 03 - Williams Road (Wabash Street - Forest Drive)

Street
Williams Road
Length (FT)
2,367

From St.
Wabash
Width (FT)
25

To. St.
Forest
Area (SY)
6,691

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	5	TON	\$100.00	\$500.00
3	HMA PATCHING, TYPE B	36.9	TON	\$150.00	\$5,535.00
4	MILLING, ASPHALT, 2 IN.	6691	SYS	\$2.10	\$14,051.10
5	MILLING, APPROACH	9.5	SYS	\$2.10	\$19.95
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	737	TON	\$75.00	\$55,275.00
7	JOINT ADHESIVE, SURFACE	2367	LFT	\$0.80	\$1,893.60
8	LIQUID ASPHALT SEALANT	2367	LFT	\$0.20	\$473.40
9	ASPHALT FOR TACK COAT	1.7	TON	\$50.00	\$85.00
10	HMA FOR APPROACHES, TYPE B	1.1	TON	\$75.00	\$82.50
11	CASTING, ADJUST TO GRADE	9	EACH	\$0.01	\$0.09
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4734	LFT	\$1.25	\$5,917.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	35	LFT	\$8.00	\$280.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	220	LFT	\$2.45	\$649.00
				TOTAL	\$83,710.15

PROJECT 05 - Freeman Street (Jackson - Fifth Street)

Street	From St.	To. St.
Freeman Street	Jackson	Fifth
Length (FT)	Width (FT)	Area (SY)
2,432	23	6,274

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	0	TON	—	—
3	HMA PATCHING, TYPE B	34.6	TON	\$150.00	\$5,190.00
4	MILLING, ASPHALT, 2 IN.	6274	SYS	\$2.10	\$13,175.40
5	MILLING, APPROACH	325.1	SYS	\$2.10	\$682.71
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	691	TON	\$75.00	\$51,825.00
7	JOINT ADHESIVE, SURFACE	2432	LFT	\$0.80	\$1,945.60
8	LIQUID ASPHALT SEALANT	2432	LFT	\$0.20	\$486.40
9	ASPHALT FOR TACK COAT	1.6	TON	\$50.00	\$80.00
10	HMA FOR APPROACHES, TYPE B	36.5	TON	\$75.00	\$2,737.50
11	CASTING, ADJUST TO GRADE	9	EACH	\$0.01	\$0.09
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	4864	LFT	\$1.25	\$6,080.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	96	LFT	\$8.00	\$768.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	336	LFT	\$2.75	\$924.00
				TOTAL	\$37,701.71

PROJECT 06 - 4th St (Freeman - 206' North (Short 4th St))

Street	From St.	To. St.
4th Street	Freeman	206' North
Length (FT)	Width (FT)	Area (SY)
206	19	426

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	0	TON	—	—
3	HMA PATCHING, TYPE B	2.4	TON	\$150.00	\$360.00
4	MILLING, ASPHALT, 2 IN.	426	SYS	\$2.10	\$894.60
5	MILLING, APPROACH	207.8	SYS	\$2.10	\$436.38
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	47	TON	\$75.00	\$3,525.00
7	JOINT ADHESIVE, SURFACE	206	LFT	\$0.80	\$164.80
8	LIQUID ASPHALT SEALANT	206	LFT	\$0.20	\$41.20
9	ASPHALT FOR TACK COAT	0.2	TON	\$50.00	\$10.00
10	HMA FOR APPROACHES, TYPE B	23.4	TON	\$75.00	\$1,755.00
11	CASTING, ADJUST TO GRADE	1	EACH	\$0.01	\$0.01
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	412	LFT	\$1.25	\$515.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	12	LFT	\$8.00	\$96.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	48	LFT	\$2.75	\$131.60
				TOTAL	\$11,871.60

PROJECT 07 - 4th Street (Walnut - Armstrong)

Street	From St.	To. St.
4th Street	Walnut	Armstrong
Length (FT)	Width (FT)	Area (SY)
1,287	27	3,887

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	0	TON	—	—
3	HMA PATCHING, TYPE B	21.4	TON	\$150.00	\$3,210.00
4	MILLING, ASPHALT, 2 IN.	3887	SYS	\$2.10	\$8,162.70
5	MILLING, APPROACH	0	SYS	—	—
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	428	TON	\$75.00	\$32,100.00
7	JOINT ADHESIVE, SURFACE	1287	LFT	\$0.80	\$1,029.60
8	LIQUID ASPHALT SEALANT	1287	LFT	\$0.20	\$257.40
9	ASPHALT FOR TACK COAT	1	TON	\$50.00	\$50.00
10	HMA FOR APPROACHES, TYPE B	0	TON	—	—
11	CASTING, ADJUST TO GRADE	5	EACH	\$0.01	\$0.05
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2574	LFT	\$1.25	\$3,217.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	96	LFT	\$8.00	\$768.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	192	LFT	\$2.95	\$566.40
	TOTAL				\$53,301.60

PROJECT 08 - Outer Drive (Crescent - Clinton)

Street	From St.	To. St.
Outer Drive	Crescent	Clinton
Length (FT)	Width (FT)	Area (SY)
1,288	29	4,104

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	0	TON	—	—
3	HMA PATCHING, TYPE B	0.7	TON	\$150.00	\$105.00
4	MILLING, ASPHALT, 2 IN.	4104	SYS	\$2.10	\$8,618.40
5	MILLING, APPROACH	126.4	SYS	\$2.10	\$2,654.40
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	451.4	TON	\$75.00	\$33,855.00
7	JOINT ADHESIVE, SURFACE	1288	LFT	\$0.80	\$1,030.40
8	LIQUID ASPHALT SEALANT	1288	LFT	\$0.20	\$257.60
9	ASPHALT FOR TACK COAT	1.1	TON	\$50.00	\$55.00
10	HMA FOR APPROACHES, TYPE B	14	TON	\$75.00	\$1,050.00
11	CASTING, ADJUST TO GRADE	5	EACH	\$0.01	\$0.05
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2576	LFT	\$1.25	\$3,220.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	48	LFT	\$8.00	\$384.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.95	\$283.20
	TOTAL				\$53,064.10

PROJECT 09 - Hawthorne Avenue (Barner - Kyger)

Street	From St.	To. St.
Hawthorne Ave.	Barner	Kyger
Length (FT)	Width (FT)	Area (SY)
1,398	19	3,016

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	15	TON	\$160.00	\$2,400.00
3	HMA PATCHING, TYPE B	16.6	TON	\$150.00	\$2,490.00
4	MILLING, ASPHALT, 2 IN.	3016	SYS	\$2.10	\$6,333.60
5	MILLING, APPROACH	65.1	SYS	\$2.10	\$1,367.10
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	332	TON	\$75.00	\$24,900.00
7	JOINT ADHESIVE, SURFACE	1398	LFT	\$0.80	\$1,118.40
8	LIQUID ASPHALT SEALANT	1398	LFT	\$0.20	\$279.60
9	ASPHALT FOR TACK COAT	0.8	TON	\$50.00	\$40.00
10	HMA FOR APPROACHES, TYPE B	7.4	TON	\$75.00	\$555.00
11	CASTING, ADJUST TO GRADE	5	EACH	\$0.01	\$0.05
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2796	LFT	\$1.25	\$3,495.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	48	LFT	\$8.00	\$384.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	48	LFT	\$2.15	\$103.20
				TOTAL	\$45,313.47

PROJECT 10 - Rowe Street (Rossville - Paris)

Street	From St.	To. St.
Rowe Street	Rossville	Paris
Length (FT)	Width (FT)	Area (SY)
1,242	25	3,465

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	15	TON	\$160.00	\$2,400.00
3	HMA PATCHING, TYPE B	19.1	TON	\$150.00	\$2,865.00
4	MILLING, ASPHALT, 2 IN.	3465	SYS	\$2.10	\$7,276.50
5	MILLING, APPROACH	152	SYS	\$2.10	\$319.20
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	382	TON	\$75.00	\$28,650.00
7	JOINT ADHESIVE, SURFACE	1242	LFT	\$0.80	\$993.60
8	LIQUID ASPHALT SEALANT	1242	LFT	\$0.20	\$248.40
9	ASPHALT FOR TACK COAT	0.9	TON	\$50.00	\$45.00
10	HMA FOR APPROACHES, TYPE B	17	TON	\$75.00	\$1,275.00
11	CASTING, ADJUST TO GRADE	5	EACH	\$0.01	\$0.05
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2484	LFT	\$1.25	\$3,105.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	60	LFT	\$8.00	\$480.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	144	LFT	\$2.15	\$309.60
				TOTAL	\$51,172.56

PROJECT 11 - Morrison Street (Pratt - Myrtle)

Street	From St.	To St.
Morrison Street	Pratt	Myrtle
Length (FT)	Width (FT)	Area (SY)
1,908	21	4,363

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	15	TON	\$100.00	\$1,500.00
3	HMA PATCHING, TYPE B	24	TON	\$150.00	\$3,600.00
4	MILLING, ASPHALT, 2 IN.	4363	SYS	\$2.10	\$9,162.30
5	MILLING, APPROACH	172.7	SYS	\$2.10	\$362.67
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	480	TON	\$75.00	\$36,000.00
7	JOINT ADHESIVE, SURFACE	1908	LFT	\$0.20	\$381.60
8	LIQUID ASPHALT SEALANT	1908	LFT	\$0.20	\$381.60
9	ASPHALT FOR TACK COAT	1.1	TON	\$50.00	\$55.00
10	HMA FOR APPROACHES, TYPE B	19.4	TON	\$75.00	\$1,455.00
11	CASTING, ADJUST TO GRADE	7	EACH	\$0.01	\$0.07
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	36	LFT	\$4.00	\$144.00
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	3816	LFT	\$1.25	\$4,770.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	20	LFT	\$8.00	\$160.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	0	LFT	—	—
	TOTAL				\$65,057.05

PROJECT 12 - Sims Street (Washington - East McClurg)

Street	From St.	To St.
Sims Street	Washington	East McClurg
Length (FT)	Width (FT)	Area (SY)
1,000	25	2,739

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	10	TON	\$100.00	\$1,000.00
3	HMA PATCHING, TYPE B	15.1	TON	\$150.00	\$2,265.00
4	MILLING, ASPHALT, 2 IN.	2739	SYS	\$2.10	\$5,751.90
5	MILLING, APPROACH	76.2	SYS	\$2.10	\$160.02
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	302	TON	\$75.00	\$22,650.00
7	JOINT ADHESIVE, SURFACE	1000	LFT	\$0.80	\$800.00
8	LIQUID ASPHALT SEALANT	1000	LFT	\$0.20	\$200.00
9	ASPHALT FOR TACK COAT	0.7	TON	\$50.00	\$35.00
10	HMA FOR APPROACHES, TYPE B	8.6	TON	\$75.00	\$645.00
11	CASTING, ADJUST TO GRADE	4	EACH	\$0.01	\$0.04
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2000	LFT	\$1.25	\$2,500.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	36	LFT	\$8.00	\$288.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.95	\$283.20
	TOTAL				\$40,512.17

PROJECT 13 - East McClurg Street (Sims - Clay)

Street From St. To St.
 East McClurg Street Sims Clay
 Length (FT) Width (FT) Area (SY)
 402 23 1,161

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	5	TON	\$100.00	\$500.00
3	HMA PATCHING, TYPE B	6.4	TON	\$150.00	\$960.00
4	MILLING, ASPHALT, 2 IN.	1161	SYS	\$2.10	\$2,438.10
5	MILLING, APPROACH	0	SYS	—	—
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	128	TON	\$75.00	\$9,600.00
7	JOINT ADHESIVE, SURFACE	1000	LFT	\$0.80	\$800.00
8	LIQUID ASPHALT SEALANT	1000	LFT	\$0.20	\$200.00
9	ASPHALT FOR TACK COAT	0.3	TON	\$50.00	\$15.00
10	HMA FOR APPROACHES, TYPE B	0	TON	—	—
11	CASTING, ADJUST TO GRADE	4	EACH	\$0.01	\$0.04
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2000	LFT	\$1.25	\$2,500.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	72	LFT	\$2.95	\$212.40
TOTAL					\$71,357.55

PROJECT 14 - East Paris Street (Jackson - Clay)

Street From St. To St.
 East Paris Street Jackson Clay
 Length (FT) Width (FT) Area (SY)
 960 26 2,733

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	8	TON	\$100.00	\$800.00
3	HMA PATCHING, TYPE B	15.1	TON	\$150.00	\$2,265.00
4	MILLING, ASPHALT, 2 IN.	2733	SYS	\$2.10	\$5,739.30
5	MILLING, APPROACH	80.3	SYS	\$2.10	\$1,686.30
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	301	TON	\$75.00	\$22,575.00
7	JOINT ADHESIVE, SURFACE	1000	LFT	\$0.80	\$800.00
8	LIQUID ASPHALT SEALANT	1000	LFT	\$0.20	\$200.00
9	ASPHALT FOR TACK COAT	0.7	TON	\$50.00	\$35.00
10	HMA FOR APPROACHES, TYPE B	9.2	TON	\$75.00	\$690.00
11	CASTING, ADJUST TO GRADE	4	EACH	\$0.01	\$0.04
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2000	LFT	\$1.25	\$2,500.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.95	\$283.20
TOTAL					\$40,182.18

PROJECT 15 - Vermont Street (Off Williams Street, runs in front of Indiana Packers)

Street From St. To St.
 Vermont Street
 Length (FT) Width (FT) Area (SY)
 600 21 1,428

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$ 3,940.00	\$ 3,940.00
2	COMPACTED AGGREGATE NO. 53	8	TON	\$ 100.00	\$ 800.00
3	HMA PATCHING, TYPE B	7.9	TON	\$ 150.00	\$ 1,185.00
4	MILLING, ASPHALT, 2 IN.	1428	SYS	\$ 2.10	\$ 2,998.80
5	MILLING, APPROACH	0	SYS	-	\$ -
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	158	TON	\$ 75.00	\$ 11,850.00
7	JOINT ADHESIVE, SURFACE	600	LFT	\$ 0.80	\$ 480.00
8	LIQUID ASPHALT SEALANT	600	LFT	\$ 0.20	\$ 120.00
9	ASPHALT FOR TACK COAT	0.4	TON	\$ 50.00	\$ 20.00
10	HMA FOR APPROACHES, TYPE B	0	TON	-	\$ -
11	CASTING, ADJUST TO GRADE	3	EACH	\$ 0.01	\$ 0.03
12	MAINTAINING TRAFFIC	1	LS	\$ 0.01	\$ 0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	-	\$ -
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1200	LFT	\$ 1.25	\$ 1,500.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	14	LFT	\$ 8.00	\$ 112.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	0	LFT	-	\$ -
TOTAL					\$ 23,005.84

PROJECT 16 - Harrison Street (Walnut - South)

Street	From St.	To. St.
Harrison Street	Walnut	South
Length (FT)	Width (FT)	Area (SY)
655	25	1,818

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$ 3,940.00
2	COMPACTED AGGREGATE NO. 53	6	TON	\$100.00	\$ 600.00
3	HMA PATCHING, TYPE B	10.1	TON	\$150.00	\$ 1,515.00
4	MILLING, ASPHALT, 2 IN.	1818	SYS	\$12.10	\$ 21,817.80
5	MILLING, APPROACH	16.7	SYS	\$22.10	\$ 369.67
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	201	TON	\$75.00	\$ 15,075.00
7	JOINT ADHESIVE, SURFACE	655	LFT	\$0.80	\$ 524.00
8	LIQUID ASPHALT SEALANT	655	LFT	\$0.20	\$ 131.00
9	ASPHALT FOR TACK COAT	0.5	TON	\$50.00	\$ 25.00
10	HMA FOR APPROACHES, TYPE B	1.9	TON	\$75.00	\$ 142.50
11	CASTING, ADJUST TO GRADE	3	EACH	\$0.01	\$ 0.03
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$ 0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	-	\$ -
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1310	LFT	\$1.25	\$ 1,637.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	30	LFT	\$8.00	\$ 240.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	48	LFT	\$2.95	\$ 141.60
				TOTAL	\$ 27,874.51

PROJECT 17 - Jefferson Street (Main - Railroad)

Street
Jefferson Street
Length (FT)
1,323

From St.
Main
Width (FT)
25

To St.
Railroad
Area (SY)
3,628

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	5	TON	\$100.00	\$500.00
3	HMA PATCHING, TYPE B	20	TON	\$150.00	\$3,000.00
4	MILLING, ASPHALT, 2 IN.	3628	SYS	\$2.10	\$7,618.80
5	MILLING, APPROACH	146.2	SYS	\$2.10	\$307.02
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	400	TON	\$75.00	\$30,000.00
7	JOINT ADHESIVE, SURFACE	1323	LFT	\$0.80	\$1,058.40
8	LIQUID ASPHALT SEALANT	1323	LFT	\$0.30	\$396.90
9	ASPHALT FOR TACK COAT	1	TON	\$50.00	\$50.00
10	HMA FOR APPROACHES, TYPE B	16.5	TON	\$75.00	\$1,237.50
11	CASTING, ADJUST TO GRADE	5	EACH	\$0.01	\$0.05
12	MAINTAINING TRAFFIC	1	LS	\$6.01	\$6.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT		
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	2646	LFT	\$1.25	\$3,307.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	96	LFT	\$8.00	\$768.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	336	LFT	\$2.75	\$921.00
TOTAL					\$53,043.06

PROJECT 18 - Harrison Street (Kyger - Green)

Street
Harrison Street
Length (FT)
727

From St.
Kyger
Width (FT)
25

To St.
Green
Area (SY)
1,999

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	6	TON	\$100.00	\$600.00
3	HMA PATCHING, TYPE B	11	TON	\$150.00	\$1,650.00
4	MILLING, ASPHALT, 2 IN.	1999	SYS	\$2.10	\$4,197.90
5	MILLING, APPROACH	47.9	SYS	\$2.10	\$100.59
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	220	TON	\$75.00	\$16,500.00
7	JOINT ADHESIVE, SURFACE	727	LFT	\$0.80	\$581.60
8	LIQUID ASPHALT SEALANT	727	LFT	\$0.30	\$218.10
9	ASPHALT FOR TACK COAT	0.5	TON	\$50.00	\$25.00
10	HMA FOR APPROACHES, TYPE B	5.6	TON	\$75.00	\$420.00
11	CASTING, ADJUST TO GRADE	3	EACH	\$0.01	\$0.03
12	MAINTAINING TRAFFIC	1	LS	\$6.01	\$6.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT		
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	1454	LFT	\$1.25	\$1,817.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	48	LFT	\$2.75	\$132.00
TOTAL					\$30,311.63

PROJECT 19 - McKinley Avenue (Walnut - Frankfort Truck & Car)

Street	From St.	To. St.
McKinley Avenue	Walnut	Frankfort Truck & Car
Length (FT)	Width (FT)	Area (SY)
2,808	24	7,523

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$ 3,940.00
2	COMPACTED AGGREGATE NO. 53	14	TON	\$100.00	\$ 1,400.00
3	HMA PATCHING, TYPE B	41.4	TON	\$150.00	\$ 6,210.00
4	MILLING, ASPHALT, 2 IN.	7523	SYS	\$2.10	\$ 15,798.30
5	MILLING, APPROACH	53.6	SYS	\$2.10	\$ 112.56
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	828	TON	\$75.00	\$ 62,100.00
7	JOINT ADHESIVE, SURFACE	2808	LFT	\$0.80	\$ 2,246.40
8	LIQUID ASPHALT SEALANT	2808	LFT	\$0.30	\$ 841.60
9	ASPHALT FOR TACK COAT	1.9	TON	\$50.00	\$ 95.00
10	HMA FOR APPROACHES, TYPE B	6.1	TON	\$75.00	\$ 457.50
11	CASTING, ADJUST TO GRADE	11	EACH	\$0.01	\$ 0.11
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$ 0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	-	\$ -
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	5616	LFT	\$1.25	\$ 7,020.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	18	LFT	\$8.00	\$ 144.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	0	LFT	-	\$ -
				TOTAL	\$100,085.48

PROJECT 20 - Short Myrtle (McKinley - Walnut)

Street From St. To St.
 Short Myrtle McKinley Walnut
 Length (FT) Width (FT) Area (SY)
 265 19 548

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$ 3,940.00
2	COMPACTED AGGREGATE NO. 53	10	TON	\$100.00	\$ 1,000.00
3	HMA PATCHING, TYPE B	3.1	TON	\$150.00	\$ 465.00
4	MILLING, ASPHALT, 2 IN.	547.8	SYS	\$2.10	\$ 1,150.38
5	MILLING, APPROACH	17.2	SYS	\$22.10	\$ 380.12
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	61	TON	\$75.00	\$ 4,575.00
7	JOINT ADHESIVE, SURFACE	265	LFT	\$0.80	\$ 212.00
8	LIQUID ASPHALT SEALANT	265	LFT	\$0.20	\$ 53.00
9	ASPHALT FOR TACK COAT	0.2	TON	\$50.00	\$ 10.00
10	HMA FOR APPROACHES, TYPE B	2	TON	\$75.00	\$ 150.00
11	CASTING, ADJUST TO GRADE	1	EACH	\$0.01	\$ 0.01
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$ 0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	\$ —
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	530	LFT	\$1.25	\$ 662.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$ 192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.95	\$ 283.20
				TOTAL	\$ 12,724.22

PROJECT 21 - Boomer Street (McKinley - Walnut)

Street From St. To St.
 Boomer Street McKinley Walnut
 Length (FT) Width (FT) Area (SY)
 264 30 886

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$ 3,940.00
2	COMPACTED AGGREGATE NO. 53	2	TON	\$100.00	\$ 200.00
3	HMA PATCHING, TYPE B	4.9	TON	\$150.00	\$ 735.00
4	MILLING, ASPHALT, 2 IN.	886	SYS	\$2.00	\$ 1,772.00
5	MILLING, APPROACH	17.2	SYS	\$2.00	\$ 34.40
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	98	TON	\$75.00	\$ 7,350.00
7	JOINT ADHESIVE, SURFACE	265	LFT	\$0.80	\$ 212.00
8	LIQUID ASPHALT SEALANT	265	LFT	\$0.20	\$ 53.00
9	ASPHALT FOR TACK COAT	0.3	TON	\$50.00	\$ 15.00
10	HMA FOR APPROACHES, TYPE B	1.9	TON	\$75.00	\$ 142.50
11	CASTING, ADJUST TO GRADE	1	EACH	\$0.01	\$ 0.01
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$ 0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	-	\$ -
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	530	LFT	\$1.25	\$ 662.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$ 192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.95	\$ 283.20
				TOTAL	\$ 15,686.44

PROJECT 22 - Calloway Ave (AKA Nickle Plate Road) (McKinley - Walnut)

Street	From St.	To. St.
Calloway Ave.	McKinley	Walnut
Length (FT)	Width (FT)	Area (SY)
267	24	722

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$ 3,940.00
2	COMPACTED AGGREGATE NO. 53	2	TON	\$100.00	\$ 200.00
3	HMA PATCHING, TYPE B	4	TON	\$150.00	\$ 600.00
4	MILLING, ASPHALT, 2 IN.	722	SYS	\$2.10	\$ 1,516.20
5	MILLING, APPROACH	11.7	SYS	\$2.10	\$ 24.57
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	80	TON	\$75.00	\$ 6,000.00
7	JOINT ADHESIVE, SURFACE	267	LFT	\$0.80	\$ 213.60
8	LIQUID ASPHALT SEALANT	267	LFT	\$0.30	\$ 80.10
9	ASPHALT FOR TACK COAT	0.2	TON	\$50.00	\$ 10.00
10	HMA FOR APPROACHES, TYPE B	1.3	TON	\$75.00	\$ 97.50
11	CASTING, ADJUST TO GRADE	1	EACH	\$0.01	\$ 0.01
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$ 0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	-	\$ -
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	534	LFT	\$1.25	\$ 667.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$8.00	\$ 192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.95	\$ 283.20
				TOTAL	\$ 13,797.91

PROJECT 23 - Eastwood Drive (Harvard - Dead End 382' South of Harvard)

Street From St. To St.
 Eastwood Drive Harvard Dead End 382' South of Harvard
 Length (FT) Width (FT) Area (SY)
 382 13 540

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	2	TON	\$100.00	\$200.00
3	HMA PATCHING, TYPE B	3	TON	\$150.00	\$450.00
4	MILLING, ASPHALT, 2 IN.	540	SYS	\$2.10	\$1,134.00
5	MILLING, APPROACH	0	SYS	—	—
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	60	TON	\$75.00	\$4,500.00
7	JOINT ADHESIVE, SURFACE	382	LFT	\$0.20	\$76.40
8	LIQUID ASPHALT SEALANT	382	LFT	\$0.20	\$76.40
9	ASPHALT FOR TACK COAT	0.2	TON	\$50.00	\$10.00
10	HMA FOR APPROACHES, TYPE B	0	TON	—	—
11	CASTING, ADJUST TO GRADE	0	EACH	—	—
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	764	LFT	\$1.25	\$955.00
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	12	LFT	\$8.00	\$96.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	0	LFT	—	—
				TOTAL	\$11,667.41

PROJECT 24 - Indiana Street (Third - Second)

Street From St. To St.
 Indiana Street Third Second
 Length (FT) Width (FT) Area (SY)
 339 17 652

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	8	TON	\$100.00	\$800.00
3	HMA PATCHING, TYPE B	3.6	TON	\$150.00	\$540.00
4	MILLING, ASPHALT, 2 IN.	652	SYS	\$2.10	\$1,369.20
5	MILLING, APPROACH	126	SYS	\$2.10	\$2,646.00
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	72	TON	\$75.00	\$5,400.00
7	JOINT ADHESIVE, SURFACE	339	LFT	\$0.20	\$67.80
8	LIQUID ASPHALT SEALANT	339	LFT	\$0.20	\$67.80
9	ASPHALT FOR TACK COAT	0.2	TON	\$50.00	\$10.00
10	HMA FOR APPROACHES, TYPE B	14	TON	\$75.00	\$1,050.00
11	CASTING, ADJUST TO GRADE	1	EACH	\$0.01	\$0.01
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	678	LFT	\$1.25	\$847.50
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	72	LFT	\$8.00	\$576.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	192	LFT	\$2.45	\$466.40
				TOTAL	\$15,700.72

PROJECT 25 - Aughe Street (Washington Clinton)

Street From St. To St.
 Aughe Street Washington Clinton
 Length (FT) Width (FT) Area (SY)
 323 23 809

PAY ITEM NO.	DESCRIPTION	QUANTITY	UNIT	UNIT COST	EXTENDED COST
1	MOBILIZATION AND DEMOBILIZATION	1	LS	\$3,940.00	\$3,940.00
2	COMPACTED AGGREGATE NO. 53	2	TON	\$10.00	\$20.00
3	HMA PATCHING, TYPE B	4.5	TON	\$150.00	\$675.00
4	MILLING, ASPHALT, 2 IN.	808.6	SYS	\$2.10	\$1,698.06
5	MILLING, APPROACH	0	SYS	—	—
6	HMA SURFACE, TYPE B, 9.5mm - 220 LB/SY	89	TON	\$75.00	\$6,675.00
7	JOINT ADHESIVE, SURFACE	323.1	LFT	\$0.80	\$258.48
8	LIQUID ASPHALT SEALANT	323.1	LFT	\$0.70	\$226.17
9	ASPHALT FOR TACK COAT	0.3	TON	\$50.00	\$15.00
10	HMA FOR APPROACHES, TYPE B	0	TON	—	—
11	CASTING, ADJUST TO GRADE	4	EACH	\$0.01	\$0.04
12	MAINTAINING TRAFFIC	1	LS	\$0.01	\$0.01
13	LINE, THERMOPLASTIC, SOLID, WHITE, 4 IN.	0	LFT	—	—
14	LINE, THERMOPLASTIC, SOLID, YELLOW, 4 IN.	646.2	LFT	\$0.75	\$484.65
15	TRANSVERSE MARKING, THERMOPLASTIC, STOP LINE, WHITE, 24 IN.	24	LFT	\$0.00	\$192.00
16	TRANSVERSE MARKING, THERMOPLASTIC, CROSSWALK, WHITE, 6 IN.	96	LFT	\$2.75	\$264.00
	TOTAL				\$12,716.72

GRAND TOTAL \$ 912,716.72

